



### West Side Fire Department -Station #2

Seismic Assessment

Prepared January 23, 2018

### **SECTION 1: INTRODUCTION**

Executive Summary1-1
ASCE 41-13 Analysis Background1-1
Scope and Limitations1-3

### **SECTION 2: ASSESSMENT**

Existing Building Description	2-1
Main Station Evaluation	2-2

### **SECTION 3: RECOMMENDATIONS**

Retrofit Recommendations
Conclusions
Cost Considerations

### APPENDICES

A. ASCE 41-13 Checklist	
B. ASCE 41-13 CalculationsB-1	
C. Seismic Retrofit SchemeC-1	
D. Cost EstimatesD-1	



### Prepared for:

West Side Fire Department 4250 Barrett Road Hood River, OR 97031

### Prepared by:

Mackenzie Attn: Tom Kay 1515 SE Water Ave., #100 Portland, OR 97214

### Project Number

2170545.00 January 23, 2018





## **1. INTRODUCTION**

IM.

### **EXECUTIVE SUMMARY**


An ASCE 41-13 Tier 1 seismic evaluation of the existing West Side Hood River Fire Station #2 was conducted for West Side Fire Department. As part of the review, a site visit was conducted on October 27th, 2017. The fire station has several significant deficiencies in the structure that do not meet the standards for a critical infrastructure building that provides a performance level of Operational after a seismic event. The primary deficiencies include an inadequate shear walls, drag connections from the shear walls to the diaphragms, and anchorage of the shear walls to the foundation. These deficiencies and the deficiencies identified in the checklists must be addressed and upgraded in order to meet Operational performance standards. A cost estimate was prepared for the proposed seismic upgrades with an anticipated total project cost as follows:

- Construction: \$818.109
- Consultants: \$335,500
- Owner: \$71.500
- Total: \$1,225,109 (\$233,53/SF)

		Project S	ummary Inf	ormation		
Building Part	Building Part Name	Included in Retrofit	Year Built	Building Type***	Nonstructural Retrofits Included in Scope Y/N***	Previous Seismic Retrofit Y/N*** (Year if Yes)
А	Apparatus Bay & Office	Y	1972	W2	Y	Ν
С	Training Room	Y	2015	W2	Y	Ν
***Entries re	quired ONLY for building parts ir	ncluded in pi	roposed seisn	nic retrofit.		
Nonstructur	al deficiencies posing life safety	risk MUST be	e included in t	the scope of	work and budget.	
0	ility inputs for existing buildings sures completed for a building p		us seismic ret	rofits MUST k	be adjusted to reflect p	revious seismic
	Total Retrofit (	Cost (\$)			\$1,225,109	
	Retrofit Square F	eet (ft^2)			5,246	
	Retrofit Cost Per Squa	re Foot (\$/ft	:^2)		\$233.53	Yes/No
Is the station documentat	n within a tsunami, FEMA flood z ion.	one or other	r high hazard	area? If so pi	rovide	No

### **ASCE 41-13 ANALYSIS BACKGROUND**

The seismic evaluation was conducted using ASCE 41-13 Seismic Evaluation and Retrofit of Existing Buildings. This document is not a code, but a nationally-recognized standard used by engineers to evaluate and retrofit existing buildings. Previously, there were two separate documents for the evaluation and retrofit of existing buildings: ASCE 31 and ASCE 41, respectively. Recently, these documents were combined into the updated version, ASCE 41-13, to help alleviate some of the inconsistencies that occurred when a







### **1. INTRODUCTION**



building made the transition from seismic evaluation to the retrofit/ upgrade process. New building codes include many provisions that require or encourage design and detailing practices that improve the seismic performance of a building, including regular building configuration, ductile detailing, and high quality materials. Most existing buildings will not meet these criteria that new construction would be designed and detailed for; however, it is recognized that these existing structural systems still have capacity that the new code doesn't recognize. The ASCE 41-13 includes guidelines and methods for evaluating the capacities of existing structural elements that might otherwise be insufficient when analyzed using the new building code provisions.

Within the ASCE 41-13 there are four building Performance Levels (lower to higher performance): Collapse Prevention (5-E), Life Safety (3-C). Immediate Occupancy (1-B), and Operational (1-A). Unless otherwise required by code (i.e., emergency response facilities, prisons, or other essential facilities), the majority of buildings are designed for the Performance Level of Life Safety (LS). The LS performance level is meant to ensure the safety of building occupants; however, buildings with this performance level will likely experience significant damage that may or may not be repaired or occupied after the earthquake. For critical facilities that need to retain full function immediately post-earthquake to provide emergency response to the community, such as a fire station, the building is evaluated to the higher standard of Operational. It should be noted that for structural evaluation the Operational and Immediate Occupancy criteria are the same. The difference in the two levels is that the support systems and equipment are operational; see Figure 1. Figure 2 includes a brief summary of each performance level and the anticipated damage for a building designed to each performance level.

ASCE 41-13 incorporates a multi-tier methodology for evaluating existing structures. Tier 1, which was chosen for this analysis, is a preliminary screening phase which utilizes a checklist approach to identify potential seismic hazards. It should be noted that at this stage, any identified risks are preliminary and may or may not be justifiable using a higher tier analysis. Tier 2 and Tier 3 are the evaluation and detailed evaluation phases, respectively, which were not conducted at this time. If a deficiency is identified in the Tier 1 screening phase, further Tier 2 or Tier 3 analysis can be used to

### **Figure 2** Damage Control and Building Performance Labels

Terret Duilding Derfermense Levels

	Target Building Performance Levels			
	Collapse Prevention Level (5-D)	Life Safety Level (3-C)	Immediate Occupancy Level (1-B)	Operational Level (1-A)
Overall damage	Severe	Moderate	Light	Very light
Structural components	Little residual stiffness and strength to resist lateral loads, but gravity load- bearing columns and walls function. Large permanent drifts. Some exits blocked. Building is near collapse in aftershocks and should not continue to be occupied.	Some residual strength and stiffness left in all stories. Gravity-load-bearing elements function. No out- of-plane failure of walls. Some permanent drift. Damage to partitions. Continued occupancy might not be likely before repair. Building might not be economical to repair.	No permanent drift. Structure substantially retains original strength and stiffness. Continued occupancy likely.	No permanent drift. Structure substantially retains original strength and stiffness. Minor cracking of facades, partitions, and ceilings as well as structural elements. All systems important to normal operation are functional. Continued occupancy and use highly likely.
Nonstructural components	Extensive damage. Infills and unbraced parapets failed or at incipient failure.	Falling hazards, such as parapets, mitigated, but many architectural, mechanical, and electrical systems are damaged.	Equipment and contents are generally secure but might not operate due to mechanical failure or lack of utilities. Some cracking of facades, partitions, and ceilings as well as structural elements. Elevators can be restarted. Fire protection operable.	Negligible damage occurs. Power and other utilities are available, possibly from standby sources.
Comparison with performance intended for typical buildings designed to codes or standards for new buildings, for the	Significantly more damage and greater life safety risk.	Somewhat more damage and slightly higher life safety risk.	Less damage and low life safety risk.	Much less damage and very low life safety risk.

show the specific item is acceptable. After the seismic evaluation is completed, ASCE 41-13 may be used to complete a seismic retrofit design to address issues identified in the evaluation stage. As a part of the Tier 1 screening phases, various analyses or "Quick Checks" are to be performed where specifically required. Not all items that pass the quick check will necessarily meet more detailed checks nor are they guaranteed to meet current code requirements.

The Tier 1 analysis consists of a visual survey, which was conducted on October 27th, 2017. For each of the Tier 1 checklist items, an evaluation of Compliant (C), Non-compliant (NC), Not Applicable (N/A), or Unknown (U) is marked. NC does not necessarily mean that the issue cannot be justified with a higher tier evaluation phase; rather, only that it does not pass the Tier 1 screening criteria.

### SCOPE AND LIMITATIONS

design earthquake

The Tier 1 analysis and retrofit scheme is based on site observations of only readily visible items and evaluation of available drawing documents listed herein. It should be noted that other deficiencies might exist that have not been identified by this screening phase and quick checks. In addition, no material or other testing was performed at this time for review. The Tier 1 quick check calculations have been performed and a more in-depth detailed analysis may be performed, though it is likely to have minimal impact on the results of this evaluation. The preliminary quick calculations of recommended retrofits were performed using ASCE 41-13 standards, which produce a conservative design for this evaluation.



## 2. ASSESSMENT

### **EXISTING BUILDING DESCRIPTION**

The West Side Fire Station #2 is located at 1185 Tucker Rd in Hood River, Oregon. The building is wood framed with an upper roof made up of open-web joists (TJL) and a lower roof made up of engineered wood I-joists (TJI) that frame into wood stud walls. The original building consists of the apparatus bay, kitchen, board room, storage, and offices. There are three (3) overhead doors in the apparatus bay, all opening to the north side of the building. A subsequent addition was added onto the original building in 2015 to include the training room. It is assumed that the framing of this addition is similar to the framing of the low roof structure adjacent to it. There is also a separate garage structure south of the fire station that was built at an unknown date. This structure is not included in the scope of this report.

Building documents for the original building dated to 1977 were available for review. Building documents for any additions were not available. A geotechnical report was unavailable for review.



**Figure 3** North elevation



Figure 4 North Elevation



Figure 5 West elevation



Figure 6 South elevation



**Figure 7** South elevation



Figure 8 East elevation



### Figure 9

Level of Seismicity Definitions

evel of Seismicity <sup>a</sup>	$S_{DS}$	$S_{D1}$
Very low	<0.167 g	<0.067 g
Low	≥0.167 g <0.33 g	≥0.067 g <0.133 g
Moderate	≥0.33 g <0.50 g	≥0.133 g <0.20 g
High	≥ 0.50 g	≥0.20 g

<sup>a</sup>The higher level of seismicity defined by S<sub>DS</sub> or S<sub>D1</sub> shall govern

**Source:** Table 2-5, page 49; ASCE Standard – ASCE/SEI 41-13: American Society of Civil Engineers – Seismic Evaluation and Retrofit of Existing Buildings

### MAIN STATION EVALUATION

### **Evaluation Criteria**

This building was evaluated for a seismic event with a probability of exceedance of 10% in 50 years or a 500-year event (BSE-1N) for a Performance Level of Operational. This is the same design earthquake ground motion hazard to which new buildings are designed. The level of seismicity was determined at the site and compared to the ASCE 41-13 level definitions; see Figure 9. For this fire station, the design 1-second period acceleration is SX1=0.319 which classifies the site as an area of high seismicity.

Based on this seismicity definition and an Operational performance objective, the required checklists can be determined, as seen in Figure 10. The Basic Configuration, Immediate Occupancy Structural Checklists, and Position Retention Nonstructural checklists are required.

ASCE 41-13 has different checklists depending on the building construction type. This building type is classified as a W1, Wood Light Frames.

### Summary of ASCE 41-13 Tier 1 Evaluation

The Tier 1 screening phase identified numerous structural and nonstructural items as non-compliant. Non-compliant issues require further evaluation in order to determine their full impact on the seismic performance of the building, but these issues are a relatively good indicator of potential performance issues. A summary of some non compliant issues is presented below organized by each checklist. Copies of the Tier 1 checklists and calculations are included in this report in Appendices A and B. In an effort to clearly document the deficiencies and their associated retrofits each item has been numbered so the reader can identify the costs.

Figure 10
Checklists Required for a Tier 1 Screening

				Require	d Checklists <sup>a</sup>		
Level of Seismicity <sup>b</sup>	Level of Building Performance <sup>°</sup>	Very Low Seismicity Checklist (Sec 16.1.1)	Basic Configuration Checklist (Sec. 16.1.2)	Life Safety Checklist (Sec. 16.2LS through 16.15LS)	Immediate Occupancy Checklist (Sec. 16.2IO through 16.15IO)	Life Safety Nonstructural Checklist (Sec. 16.17)	Position Retention Nonstructural Checklist (Sec. 16.17)
Very low	LS	Х					
Very low	IO		Х		Х		Х
Low	LS		Х	Х		Х	
Low	IO		Х		Х		Х
Moderate	LS		Х	Х		Х	
Moderate	IO		Х		Х		Х
High	LS		Х	Х		Х	
High	IO		Х		Х		Х

<sup>*a*</sup>An X designates the checklist that must be completed for a Tier 1 screening as a function of the level of seismicity and level of performance. <sup>*b*</sup>Defined in Section 2.5.

LS = Life Safety Performance Level, and IO = Immediate Occupancy Performance Level (defined in Section 2.3.3).

**Source:** Table 4-7, page 67; ASCE Standard – ASCE/SEI 41-13: American Society of Civil Engineers – Seismic Evaluation and Retrofit of Existing Buildings

### West Side Fire Department - Station #2

January 23, 2018

### Immediate Occupancy Basic Configuration Checklist

**Load Path –** A clear lateral load path to transfer seismic forces from the walls, into the roof diaphragm, into the main lateral force resisting system, and then out into the foundations is required for compliance. The existing diaphragm is deficient, and there is no element to transfer seismic loads into the shear walls in most cases. The lateral force resisting system is deficient in several areas, particularly along the north wall in the apparatus bay which has several large openings for overhead doors. At this location, the existing footing is not large enough to resist overturning forces and exceeds the allowable seismic bearing pressure.

### Immediate Occupancy Structural Checklist for Building Type W2

- Shear Stress Check Existing shear walls are assumed to be unblocked, with either structural or non-structural sheathing, resulting in low capacities.
- Narrow Wood Shear Walls/Openings North shear walls in apparatus bay have several openings for windows. Therefore the walls do not pass the quick check and have a height to width ratio greater than 1.5:1, which increases the likelihood of overturning.
- Hold-Down Anchors It is assumed that shear walls do not have hold downs to resist overturning forces at each pier.
- **Diaphragm Continuity** The building is composed of split-level roofs with no elements to provide shear transfer at the vertical offset of the diaphragm.
- **Roof Chord Continuity** There do not appear to be any continuous chord elements throughout the building's diaphragm.
- **Plan Irregularities** At the lower roof, there are no drag elements at re-entrant corners to deliver the seismic forces into the lateral force resisting element.
- Wood Sill Bolts Existing drawings indicate bolts at 5'-0" on center for the original building. It is assumed that the later addition is at this spacing or greater.

### **Non-Structural Checklist**

- **Fire Suppression Piping** Fire suppression piping should have proper lateral bracing and flexible couplings when necessary. It appeared some bracing was in place, but a further study may be necessary to determine if it is adequate.
- Hazardous Materials and Shut-off Valves Gas cylinders and other hazardous materials should be tied down to prevent movement. It did appear that several were tied down, but other conditions were unknown. If any distribution systems carry hazardous materials, they should have shut-off valves.



- Integrated Ceilings, Edge Clearance and Support Suspended ceilings in meeting room should have proper lateral restraints and allow for lateral movement.
- Light Fixtures Lens Covers Light fixtures should have lens covers attached with safety devices to catch falling debris from the light fixture.
- Panel Connections Panel fastening is unknown. Removal of siding and new panels will allow for the opportunity to properly attach panels to walls.
- **Tall Narrow Contents** Several shelving units, storage units, and pieces of equipment appear to have a height-to-width ratio greater than 3:1 and are not anchored to the floor or walls. During a seismic event, these pose a falling hazard.
- Fall Prone Contents Equipment or stored items weighing more than 20 lbs and located more than 4 ft above the floor should be braced or anchored to structure. A detailed survey of equipment/ contents was not conducted, but some stored items appear to have met these criteria.
- Suspended Contents/Equipment Equipment suspended without lateral bracing should be to swing from or move with the structure from which it is suspended without damaging other components.
- **Mechanical Doors** It is unknown if the apparatus bay doors of this station are detailed to operate at a story drift ratio of 0.01, which could leave the doors inoperable after a seismic event.
- Heavy Equipment Floor-supported equipment weighing more than 400 lbs should be anchored to the structure. It appeared that most of the equipment was properly anchored, but this should be investigated further.
- Flexible Couplings Fluid and gas piping should have flexible couplings to accommodate any lateral movement. It appeared that flexible couplings were installed at a few locations, however more may be necessary at critical areas.
- **Piping** Fluid and gas piping should be anchored and braced to the structure to limit spills or leaks. A detailed investigation was not conducted; however, only some piping was noted to meet this requirement.
- Ducts Large ducts should be braced. The maximum unbraced span should not exceed 30 ft.

# **3. RECOMMENDATIONS**

### **RETROFIT RECOMMENDATIONS**

Prior to retrofitting and design, material testing of key structural elements must be completed as required by ASCE 41-13 for a performance level greater than life safety.

The Tier 1 structural deficiencies listed will require further evaluation (ASCE 41-13 Tier 2 or 3 analyses) for the design of the seismic retrofits listed below. For a facility, such as a fire station, to meet the Operational Performance Level, each of these items will need to be further evaluated and brought up to meet current code requirements. The following narrative describes the approximate scope of one possible upgrade scheme to address the identified deficiencies. Plans and details of the upgrade scheme are provided in Appendix C.

### **Structural Retrofits:**

- Task 1: There is inadequate lateral support at the north side of the apparatus bay. Add two special moment frames at the existing bay doors. A continuous grade beam below the moment frame should be included to limit structure drift. Demolition of the existing slab as well as the existing building's foundations will need to occur to install the moment frame footings. Slab on grade to be replaced. Since there is some concern about the apparatus bay doors meeting the required thermal and seismic criteria, new apparatus bay doors are to be installed that will comply with current code criteria. See the Foundation/Roof Retrofit Plan for details and locations.
- Task 2: Where walls have structural sheathing, wood shear walls should be blocked and re-nailed with smaller nail spacing. Where walls have non-structural sheathing, wood shear walls should be blocked, re-sheathed with structural sheathing. and re-nailed with smaller nail spacing. See the Foundation Retrofit Plan for details and locations. Hold-downs should be added on each side of wood shear wall piers. Holddowns (Figure 11) should be a Simpson HTT5 or equivalent with epoxy anchorage into existing foundation. See the Foundation Retrofit Plan for details and locations. Additional sill anchors need to be added at wood shear walls to connect them to their foundations. The on-center spacing of sill bolts should be 3 feet on center or less. Provide strapping above and below windows so lateral forces can be properly transferred to adjacent wall piers. Remove existing roofing, and provide additional nailing @ 4" on center into the existing diaphragm. See the Roof Retrofit Plan for details.
- Task 3: There is no positive connection between the roof diaphragm and the shear walls. At the high roof, provide wood stud wall infill per SK3. At low roof, provide blocking infill per SK1 and SK2.




Figure 11 Simpson Hold Down



- Task 4: Provide continuous chord elements at both the high roof and the low roof. See Roof Retrofit Plan for details and locations.
- Task 5: Drag elements are required at the low roof at re-entrant corners. See Foundation/Roof Retrofit Plan for details & locations.

### **Non-Structural Retrofits:**

- Task 6: The purpose of this report and site visit was primarily a structural seismic assessment of the main station. If the decision is made to seismically retrofit and continue using the main station, a more detailed survey of nonstructural components (ceilings, fire suppression systems, mechanical systems, light fixtures, etc.) should be made and any deficiencies should be addressed. The list below addresses some possible non-structural deficiencies and general solutions.Hazardous Materials: Gas cylinders and storage tanks should be restrained from lateral movement. It appeared that many of the gas cylinders were placed in cabinets; however, some hazardous material storage tanks may not be properly secured. Ensure shut-off valves are available for distributed hazardous materials (natural gas, gasoline, etc.) or are operational if present.
  - Life Safety Systems: Emergency power to be anchored to slabs or supplement bracing added to prevent lateral movement. Emergency lighting should be properly anchored to walls or laterally braced to structure if hanging lights are present. Verify that fire suppression piping is properly braced.
  - Hazardous Materials: Gas cylinders and storage tanks should be restrained from lateral movement. It appeared that many of the gas cylinders were placed in cabinets; however some hazardous material storage tanks may not be properly secured. Ensure shut-off valves are available for distributed hazardous materials (natural gas, gasoline, etc.) or are operational if present.Cladding: Provide proper attachment of exterior panels to structure. Ensure glazing with appropriate specifications is used.
  - Ceilings: Supplemental attachments of gypsum board/ lath and plaster ceiling systems may be required. Add screws or nails as necessary. Provide edge distances and support for suspended ceilings, add lateral bracing if necessary.
  - Light Fixtures: Add lens covers to light fixtures as required.
  - Cladding: Provide proper attachment of exterior panels to structure. Ensure glazing with appropriate specifications is used.

- Contents & Furnishings: Use shelf lips on storage racks, bungee cords, wires, or anchorage to slab for contents that is likely to fall or tip in a seismic event.
- Mechanical & Electrical Equipment: Ensure proper slab anchorage for air compressor, water heater, and other mechanical equipment that is critical to station operations.
- Ducts/Piping: Mechanical ducts or fluid/gas piping should be properly braced to restrain lateral movement. Flexible couplings should be added to pipes at attachment to appliances or similar to allow movement.
- Architectural elements affected by the structural retrofit may have to be replaced due to demolition or access issues when applying the structural retrofit recommendations. This includes, but is not limited to, roofing, siding, and new paint.

	Task Sumn	Drawings		
Task #	Deficiency	Description	Keynote #	SK#
1	Load Path Narrow Wood Shear Walls Shear Stress Check	North side of high roof does not have a sufficient amount of shear wall to resist seismic forces. (2) bay moment frame required @ this location.	7, 8, 9, 10, 12	4
2	Shear Stress Check Hold Down Anchors Wood Sill Bolts	Existing wood shear walls & diaphragms do not have enough capacity to resist seismic loads. There is no hold-down anchorage to resist overturning. Wood sill bolts are not compliant.	1, 2, 3, 4, 5, 6, 15	_
3	Load Path Diaphragm Continuity	There is not sufficient blocking to tie the roof diaphragms to shear.	-	1, 2, 3
4	Roof Chord Continuity	There are no continuous chord elements.	16	3
5	Plan Irregularities	There are no drag elements @ re-entrant corners.	11, 13, 14	-
6	Life Safety Systems Hazardous Materials Ceilings Light Fixtures Cladding Furnishings Mechanical & Electrical Ducts & Piping	Non-structural components are not properly braced or restrained to prevent lateral movement during a seismic event.	-	-

### CONCLUSIONS

The Tier 1 analysis has revealed that the building has multiple structural and non-structural seismic deficiencies which would not meet the current seismic design standards for an essential facility. Based on the site and the existing building information available at this time, the retrofit would address the deficiencies identified in the Tier 1 checklists to meet Operational standards. A thorough, Tier 2 analysis of the building in conjunction with materials testing and geotechnical investigation would need to be conducted to provide comprehensive upgrade design for the facility. The complete analysis and design development for those repairs is an effort that is beyond the scope of this investigation. Depending on the results of this additional analysis/investigation, there may be changes to the list of repairs above. Functionality and fire life safety deficiencies have not been addressed and are outside the scope of this report.

Once a complete analysis and design of a seismic upgrade has been submitted and construction has been completed, the West Side Fire Station #2 can expect to remain occupied and functional after a seismic event of the size expected in the region.

### COST CONSIDERATIONS

Following completion of the seismic assessment, Mackenzie evaluated cost impacts of the rehabilitation scheme. The following cost summary projects a total development cost, including estimated construction costs, design costs, and owner costs.

**Development costs** of a project are not limited to construction costs alone and require consideration of other variables. These variables differ between new construction and renovation or expansion, and invariably change from one project to the next depending on site conditions, existing building conditions, building codes, seismic zones, and the environment of the construction industry. While differences arise depending on the design approach taken, the construction costs, design and engineering costs, and owner costs for furniture, fixtures and equipment are constants. New construction can often differ substantially due to the single variable of land acquisition.

**Construction costs** reflect the raw costs incurred by a general contractor for overhead and profit, bonding and insurance, securing of materials and general construction of the site and building. In addition to the identified construction costs, an escalation cost that reflects the expected start of construction has been added. Furthermore, a design contingency is recommended to ensure dollars are carried through construction for owner changes, design omissions, unforeseen conditions or jurisdictional requirements, among others.

**Consultant costs** reflect the costs incurred for project management and design of the project from conceptual design through construction administration. Though design fees can vary, these costs are generally factored using a fee based on the construction costs for the project. In addition to architectural and engineering services, costs include marketing materials and required services such as geotechnical analysis and special inspections. A contingency is provided for this category for any unforeseen or additionally requested design and/or engineering services throughout the project.

**Owner costs** reflect the costs generally incurred directly by the owner throughout the project. This includes all items the owner will likely need to contract separately from the general construction of the project. Additional owner-related costs include land costs, equipment and furnishing costs, relocation into the new facility, legal documentation and counsel for project documents and issuances, and jurisdictional fees associated with design review, building permits, and L&I fees. A contingency is provided in this category for any unforeseen or undefined costs not currently represented.

The following project development cost estimate examines the construction values of the programmed design concept based on the anticipated Construction, Consultant, and Owner Costs. Detailed break-out of the anticipated construction costs and permit costs have been provided in Appendix D to describe elements proposed.



### **Project Cost Summary**

### West Side Fire Station 2 - Project Cost Summary

12/18/2017

	Comments
Construction Cost of Facil	lity
General Contractor Construction Cost	\$434,823 \$82.89 per SF
Escalation Start of Construction - Fall 2019	\$52,179 12% 6% per year
Construction Contingency	\$146,100 30%
General Conditions	\$60,661 9%
CMGC Process	\$40,910 5%
Profit & Overhead	\$73,467 9%
Bonds & Insurances	\$9,968 1%
Total Construction Costs	\$818,109 \$155.95 per SF
Consultants Costs	
A/E Design	\$135,000 17% of GCC Cost
Reimbursables	\$13,500 10% of A/E Design and Construction
As-builting building	\$5,000 Allowance
A/E LEED Design and Documentation	\$0 Not required
CM/GC Preconstruction Services	\$35,000 Allowance 5k per month
Owner's Project Manager	\$35,000 4% of GC Cost
Topo and Boundary Survey	\$3,500 Allowance
ASCE 41 Materials Testing	\$10,000 Allowance
Special Inspections	\$16,000 Estimate
Geotechnical Services	\$20,000 Estimate
Environmental Services	\$0 Not required
Hazardous Material Survey/Testing/Mitigation Specs	\$12,000 Estimate
Abatement	\$20,000 Estimate
Subtotal - Consultants	\$305,000
Consultants Contingency	\$30,500 10% of Consultants Costs
Total Consultants Costs	\$335,500 \$63.95 per SF
Owner Costs	
Lawyer Contract Review	\$7,500 Allowance
Fixtures, Furniture & Equipment (FF&E)	\$15,000 Estimated to replace
Moving Allowance	\$7,500 Move to temporary facility
Temporary Facilities	\$25,000 Tents for apparatus
Permit Fees	\$10,000 Estimate
Subtotal - Owner Costs	\$65,000
Owner Contingency	\$6,500 10% of Owner Costs
Total Owner Costs	\$71,500 \$13.63 per SF

### Total Project Cost

\$1,225,109 \$233.53 per SF

Building Size:


Exclusions: Off-site improvements to public right-of-way or utilities

5,246 SF

January 23, 2018

### **ASCE 41-13 CHECKLIST**

A. ASCE 41-13 CHECKLIST





	IVER STATION 2     Location: <u>1185 TUCKER RD, HOOD RIVER OR 97031</u>
Completed by: <u>S</u>	W         Date:         NOVEMBER 8, 2017
	DIATE OCCUPANCY BASIC CONFIGURATION CHECKLIST
Very Low Seismic Building System	ity
General	
C NC N/A U	LOAD PATH: The structure shall contain a complete, well-defined load path, including structural elements and connections, that serves to transfer the inertial forces associated with the mass of all elements of the building to the foundation. (Commentary: Sec. A.2.1.1. Tier 2: Sec. 5.4.1.1)
C NC N/A U	ADJACENT BUILDINGS: The clear distance between the building being evaluated and any adjacent building is greater than 4% of the height of the shorter building. This statement need not apply for the following building types: W1, W1a, and W2. (Commentary: Sec. A.2.1.2. Tier 2: Sec. 5.4.1.2)
C NC N/A U	MEZZANINES: Interior mezzanine levels are braced independently from the main structure or are anchored to the seismic-force-resisting elements of the main structure. (Commentary: Sec. A.2.1.3. Tier 2: Sec. 5.4.1.3)
Building Configura	tion
C NC N/A U	WEAK STORY: The sum of the shear strengths of the seismic-force-resisting system in any story in each direction shall not be less than 80% of the strength in the adjacent story above. (Commentary: Sec. A.2.2.2. Tier 2: Sec. 5.4.2.1)
C NC N/A U	SOFT STORY: The stiffness of the seismic-force-resisting system in any story shall not be less than 70% of the seismic-force-resisting system stiffness in an adjacent story above or less than 80% of the average seismic-force-resisting system stiffnessof the three stories above. (Commentary: Sec. A.2.2.3. Tier 2: Sec. 5.4.2.2)
C NC N/A U	VERTICAL IRREGULARITIES: All vertical elements in the seismic-force-resisting system are continuous to the foundation. (Commentary: Sec. A.2.2.4. Tier 2: Sec. 5.4.2.3)
C NC N/A U	GEOMETRY: There are no changes in the net horizontal dimension of the seismic-force-resisting system of more than 30% in a story relative to adjacent stories, excluding one-story penthouses and mezzanines. (Commentary: Sec. A.2.2.5. Tier 2: Sec. 5.4.2.4)
C NC N/A U	MASS: There is no change in effective mass more than 50% from one story to the next. Light roofs, penthouses, and mezzanines need not be considered. (Commentary: Sec. A.2.2.6. Tier 2: Sec. 5.4.2.5)
C NC N/A U	TORSION: The estimated distance between the story center of mass and the story center of rigidity is less than 20% of the building width in either plan dimension. (Commentary: Sec. A.2.2.7. Tier 2: Sec. 5.4.2.6)
Low Seismicity: C	omplete the Following Items in Additionto the Items for Very Low Seismicity.
Geologic Site Haz	ards
C NC N/AU	LIQUEFACTION: Liquefaction-susceptible, saturated, loose granular soils that could jeopardize the building's seismic performance shall not exist in the foundation soils at depths within 50 ft under the building. (Commentary: Sec. A.6.1.1. Tier 2: 5.4.3.1)
C NC N/A U	SLOPE FAILURE: The building site is sufficiently remote from potential earthquake-induced slope failures or rockfalls to be unaffected by such failures or is capable of accommodating any predicted movements without failure. (Commentary: Sec. A.6.1.2. Tier 2: 5.4.3.1)
C NC N/A U	SURFACE FAULT RUPTURE: Surface fault rupture and surface displacement at the building site are not anticipated. (Commentary: Sec. A.6.1.3. Tier 2: 5.4.3.1)
Moderate and Hig	h Seismicity: Complete the Following Items in Addition to the Items for Low Seismicity.
Foundation Config	guration
C NC N/A U	OVERTURNING: The ratio of the least horizontal dimension of the seismic-force-resisting system at the foundation level to the building height (base/height) is greater than $0.6S_a$ . (Commentary: Sec. A.6.2.1. Tier 2: Sec. 5.4.3.3)
C NC N/AU	TIES BETWEEN FOUNDATION ELEMENTS: The foundation has ties adequate to resist seismic forces where footings, piles, and piers are not restrained by beams, slabs, or soils classified as Site Class A, B, or C. (Commentary: Sec. A.6.2.2. Tier 2: Sec. 5.4.3.4)


Project: HOOD RIV	VER STATION 1 Location: 1185 TUCKER RD, HOOD RIVER OR 970	31
Completed by: SIW	Date: NOVEMBER 8, 2017	
	ATE OCCUPANCY STRUCTURAL CHECKLIST FOR BUILDING TYPE W2: WOOD FRAME RCIAL AND INDUSTRIAL ity	S,
Seismic-Force-Resi	isting System	
C NC N/A U	REDUNDANCY: The number of lines of shear walls in each principal direction is greater than or eq (Commentary: Sec. A.3.2.1.1. Tier 2: Sec. 5.5.1.1)	ual to 2.
C NC N/A U	SHEAR STRESS CHECK: The shear stress in the shear walls, calculated using the Quick Check pro Section 4.5.3.3, is less than the following values (Commentary: Sec. A.3.2.7.1. Tier 2: Sec. 5.5.3.1.1)	
	Structural panel sheathing1,000 lb/ftDiagonal sheathing700 lb/ftStraight sheathing100 lb/ftAll other conditions100 lb/ft	
C NC N/A U	STUCCO (EXTERIOR PLASTER) SHEAR WALLS: Multi-story buildings do not rely on exterior s walls as the primary seismic-force-resisting system. (Commentary: Sec. A.3.2.7.2. Tier 2: Sec. 5.5.3.0)	
C NC N/A U	GYPSUM WALLBOARD OR PLASTER SHEAR WALLS: Interior plaster or gypsum wallboard is as shear walls on buildings more than one story high with the exception of the uppermost level of a story building. (Commentary: Sec. A.3.2.7.3. Tier 2: Sec. 5.5.3.6.1)	
C NC N/A U	NARROW WOOD SHEAR WALLS: Narrow wood shear walls with an aspect ratio greater than 2-to not used to resist seismic forces. (Commentary: Sec. A.3.2.7.4. Tier 2: Sec. 5.5.3.6.1)	-1 are
C NC N/A U	WALLS CONNECTED THROUGH FLOORS: Shear walls have an interconnection between stories transfer overturning and shear forces through the floor. (Commentary: Sec. A.3.2.7.5. Tier 2: Sec. 5.5.	
C NC N/A U	HILLSIDE SITE: For structures that are taller on at least one side by more than one-half story becau sloping site, all shear walls on the downhill slope have an aspect ratio less than 1-to-2. (Commentary A.3.2.7.6. Tier 2: Sec. 5.5.3.6.3)	
C NC N/A U	CRIPPLE WALLS: Cripple walls below first-floor-level shear walls are braced to the foundation with structural panels. (Commentary: Sec. A.3.2.7.7. Tier 2: Sec. 5.5.3.6.4)	ı wood
C NC N/A U	OPENINGS: Walls with openings greater than 80% of the length are braced with wood structural par walls with aspect ratios of not more than 1.5-to-1 or are supported by adjacent construction through ties capable of transferring the seismic forces. (Commentary: Sec. A.3.2.7.8. Tier 2: Sec. 5.5.3.6.5)	
C NC N/A U	HOLD-DOWN ANCHORS: All shear walls have hold-down anchors, constructed per acceptable con practices, attached to the end studs. (Commentary: Sec. A.3.2.7.9. Tier 2: Sec. 5.5.3.6.6)	struction
Connections		
C NC N/A U	WOOD POSTS: There is a positive connection of wood posts to the foundation. (Commentary: Sec. Tier 2: Sec. 5.7.3.3)	A.5.3.3.
C NC N/A U	WOOD SILLS: All wood sills are bolted to the foundation. (Commentary: Sec. A.5.3.4. Tier 2: Sec.	5.7.3.3)
C NC N/A U	GIRDER/COLUMN CONNECTION: There is a positive connection using plates, connection hardwas straps between the girder and the column support. (Commentary: Sec. A.5.4.1. Tier 2: Sec. 5.7.4.1)	re, or
Foundation System	n	
C NC N/A U	DEEP FOUNDATIONS: Piles and piers are capable of transferring the lateral forces between the struthe soil. (Commentary: Sec. A.6.2.3.)	icture an
C NC N/A U	SLOPING SITES: The difference in foundation embedment depth from one side of the building to an shall not exceed one story high. (Commentary: Sec. A.6.2.4)	other



$\sim$	orce-	ivesi	isting System
	N/A	U	NARROW WOOD SHEAR WALLS: Narrow wood shear walls with an aspect ratio greater than 1.5-to-1 are not used to resist seismic forces. (Commentary: Sec. A.3.2.7.4. Tier 2: Sec. 5.5.3.6.1)
Diaphrag	ms		
C NC	N/A	U	DIAPHRAGM CONTINUITY: The diaphragms are not composed of split-level floors and do not have expansion joints. (Commentary: Sec. A.4.1.1. Tier 2: Sec. 5.6.1.1)
C NC	N/A	U	ROOF CHORD CONTINUITY: All chord elements are continuous, regardless of changes in roof elevation. (Commentary: Sec. A.4.1.3. Tier 2: Sec. 5.6.1.1)
C NC	N/A	U	PLAN IRREGULARITIES: There is tensile capacity to develop the strength of the diaphragm at reentrant corners or other locations of plan irregularities. (Commentary: Sec. A.4.1.7. Tier 2: Sec. 5.6.1.4)
C NC	N/A	U	DIAPHRAGM REINFORCEMENT AT OPENINGS: There is reinforcing around all diaphragm openings larger than 50% of the building width in either major plan dimension. (Commentary: Sec. A.4.1.8. Tier 2: Sec. 5.6.1.5)
C NC	N/A	U	STRAIGHT SHEATHING: All straight sheathed diaphragms have aspect ratios less than 1-to-1 in the direction being considered. (Commentary: Sec. A.4.2.1. Tier 2: Sec. 5.6.2)
NC	N/A	U	SPANS: All wood diaphragms with spans greater than 12 ft consist of wood structural panels or diagonal sheathing. Wood commercial and industrial buildings may have rod-braced systems. (Commentary: Sec. A.4.2.2. Tier 2: Sec. 5.6.2)
C NC	N/A	U	DIAGONALLY SHEATHED AND UNBLOCKED DIAPHRAGMS: All diagonally sheathed or unblocked wood structural panel diaphragms have horizontal spans less than 30 ft and aspect ratios less than or equal to 3-to-1. (Commentary: Sec. A.4.2.3. Tier 2: Sec. 5.6.2)
C NC	N/A	U	OTHER DIAPHRAGMS: The diaphragm does not consist of a system other than wood, metal deck, concrete or horizontal bracing. (Commentary: Sec. A.4.7.1. Tier 2: Sec. 5.6.5)
Connectio	ons		
C NC	N/A	U	WOOD SILL BOLTS: Sill bolts are spaced at 4 ft or less, with proper edge and end distance provided for wood and concrete. (Commentary: Sec. A.5.3.7. Tier 2: Sec. 5.7.3.3)

Project: HOOD RIVER STATION 2	Location: 1185 TUCKER RD, HOOD RIVER OR 97031
Completed by: SIW	Date: NOVEMBER 8, 2017
16.17 NONSTRUCTURAL CHECKLIST	
Life Safety Systems	
	RESSION PIPING: Fire suppression piping is anchored and braced in nentary: Sec. A.7.13.1. Tier 2: Sec. 13.7.4)
C NC N/A U LS-LMH; PR-LMH. FLEXIBLE C with NFPA-13. (Commentary: Sec	COUPLINGS: Fire suppression piping has flexible couplings in accordance . A.7.13.2. Tier 2: Sec. 13.7.4)
C NC N/A ULS-LMH; PR-LMH. EMERGENC anchored or braced. (Commentary	CY POWER: Equipment used to power or control life safety systems is : Sec. A.7.12.1. Tier 2: Sec. 13.7.7)
	SMOKE DUCTS: Stair pressurization and smoke control ducts are braced eismic joints. (Commentary: Sec. A.7.14.1. Tier 2: Sec. 13.7.6)
	EILING CLEARANCE: Penetrations through panelized ceilings for fire unces in accordance with NFPA-13. (Commentary: Sec. A.7.13.3. Tier 2:
C NC N/A U LS-not required; PR-LMH. EMER or braced. (Commentary: Sec. A.7	GENCY LIGHTING: Emergency and egress lighting equipment is anchore .3.1. Tier 2: Sec. 13.7.9)
Hazardous Materials	
	JS MATERIAL EQUIPMENT: Equipment mounted on vibration isolators is equipped with restraints or snubbers. (Commentary: Sec. A.7.12.2. Tier
	JS MATERIAL STORAGE: Breakable containers that hold hazardous are restrained by latched doors, shelf lips, wires, or other methods. 2: Sec. 13.8.4)
	MATERIAL DISTRIBUTION: Piping or ductwork conveying hazardous rotected from damage that would allow hazardous material release. 2: Sec. 13.7.3 and 13.7.5)
C NC N/A U LS-MH; PR-MH. SHUT-OFF VAI off valves or other devices to limit	LVES: Piping containing hazardous material, including natural gas, has shut spills or leaks. (Commentary: Sec. A.7.13.3. Tier 2: Sec. 13.7.3 and 13.7.5
C NC N/A U LS-LMH; PR-LMH. FLEXIBLE C gas piping, has flexible couplings.	COUPLINGS: Hazardous material ductwork and piping, including natural (Commentary: Sec. A.7.15.4, Tier 2: Sec.13.7.3 and 13.7.5)
hazardous material that either cros	ICTS CROSSING SEISMIC JOINTS: Piping or ductwork carrying sees seismic joints or isolation planes or is connected to independent letails to accommodate the relative seismic displacements. (Commentary: 13.7.5, and 13.7.6)
Partitions	
	RCED MASONRY: Unreinforced masonry or hollow-clay tile partitions are ft in Low or Moderate Seismicity, or at most 6 ft in High Seismicity. Sec. 13.6.2)
	TITIONS SUPPORTED BY CEILINGS: The tops of masonry or hollow- y supported by an integrated ceiling system. (Commentary: Sec. A.7.2.1. Tie
	ementitious partitions are detailed to accommodate the following drift ration noment frame, and wood frame buildings, 0.02; in other buildings, 0.005.





### West Side Fire Department - Station #2


С	NC	N/A	U	LS-MH; PR-MH. MULTI-STORY PANELS: For multi-story panels attached at more than one floor level, panel connections are detailed to accommodate a story drift ratio of at least the following: for Life Safety Moderate Seismicity, 0.01; for Life Safety in High Seismicity and for Position Retention in any seismicty, 0.02. (Commentary: Sec. A.7.4.4. Tier 2: Sec. 13.6.1)
С	NC	N/A	U	LS-MH; PR-MH. PANEL CONNECTIONS: Cladding panels are anchored out-of-plane with a minimum number of connections for each wall panel, as follows: for Life Safety in Moderate Seismicity, 2 connection for Life Safety in High Seismicity and for Position Retention in any seismicity, 4 connections. (Commenta Sec. A.7.4.5. Tier 2: Sec. 13.6.1.4)
С	NC	N/A	U	LS-MH; PR-MH. BEARING CONNECTIONS: Where bearing connections are used, there is a minimum of two bearing connections for each cladding panel. (Commentary: Sec. A.7.4.6. Tier 2: Sec. 13.6.1.4)
С	NC	N/A	U	LS-MH; PR-MH. INSERTS: Where concrete cladding components use inserts, the inserts have positive anchorage or are anchored to reinforcing steel. (Commentary: Sec. A.7.4.7. Tier 2: Sec. 13.6.1.4)
C	NC	N/A	U	LS-MH; PR-MH. OVERHEAD GLAZING: Glazing panes of any size in curtain walls and individual inter or exterior panes over 16 ft <sup>2</sup> in area are laminated annealed or laminated heat-strengthened glass and are detailed to remain in the frame when cracked. (Commentary: Sec. A.7.4.8: Tier 2: Sec. 13.6.1.5)
Ma	sonry	y Vene	er	
С	NC	N/A	U	LS-LMH; PR-LMH. TIES: Masonry veneer is connected to the backup with corrosion-resistant ties. There minimum of one tie for every 2-2/3 ft <sup>2</sup> , and the ties have spacing no greater than the following: for Life Sa in Low or Moderate Seismicity, 36 in.; for Life Safety in High Seismicity and for Position Retention in any seismicity, 24 in. (Commentary: Sec. A.7.5.1. Tier 2: Sec. 13.6.1.2)
С	NC	N/A	U	LS-LMH; PR-LMH. SHELF ANGLES: Masonry veneer is supported by shelf angles or other elements at a floor above the ground floor. (Commentary: Sec. A.7.5.2. Tier 2: Sec. 13.6.1.2)
С	NC	N/A	U	LS-LMH; PR-LMH. WEAKENED PLANES: Masonry veneer is anchored to the backup adjacent to weakened planes, such as at the locations of flashing. (Commentary: Sec. A.7.5.3. Tier 2: Sec. 13.6.1.2)
С	NC	N/A	U	LS-LMH; PR-LMH. UNREINFORCED MASONRY BACKUP: There is no unreinforced masonry backup (Commentary: Sec. A.7.7.2. Tier 2: Section 13.6.1.1 and 13.6.1.2)
С	NC	N/A	U	LS-MH; PR-MH. STUD TRACKS: For veneer with metal stud backup, stud tracks are fastened to the structure at a spacing equal to or less than 24 in. on center. (Commentary: Sec. A.7.6.1. Tier 2: Section 13.6.1.1 and 13.6.1.2)
C	NC	N/A	U	LS-MH; PR-MH. ANCHORAGE: For veneer with concrete block or masonry backup, the backup is positi anchored to the structure at a horizontal spacing equal to or less than 4 ft along the floors and roof. (Commentary: Sec. A.7.7.1. Tier 2: Section 13.6.1.1 and 13.6.1.2)
С	NC	N/A	U	LS-not required; PR-MH. WEEP HOLES: In veneer anchored to stud walls, the veneer has functioning we holes and base flashing. (Commentary: Sec. A.7.5.6. Tier 2: Section 13.6.1.2)
С	NC	N/A	U	LS-not required; PR-MH. OPENINGS: For veneer with metal stud backup, steel studs frame window and openings. (Commentary: Sec. A.7.6.2. Tier 2: Sec. 13.6.1.1 and 13.6.1.2)
Pa	rapets	s, Corr	nices,	, Ornamentation, and Appendages
С	NC	N/A	U	LS-LMH; PR-LMH. URM PARAPETS OR CORNICES: Laterally unsupported unreinforced masonry parapets or cornices have height-to-thickness ratios no greater than the following: for Life Safety in Low or Moderate Seismicity, 2.5; for Life Safety in High Seismicity and for Position Retention in any seismicity, (Commentary: Sec. A.7.8.1. Tier 2: Sec. 13.6.5)
C	NC	N/A	U	LS-LMH; PR-LMH. CANOPIES: Canopies at building exits are anchored to the structure at a spacing no greater than the following: for Life Safety in Low or Moderate Seismicity, 10 ft; for Life Safety in High Seismicity and for Position Retention in any seismicity, 6 ft. (Commentary: Sec. A.7.8.2. Tier 2: Sec. 13.6.
С	NC	N/A	U	LS-MH; PR-LMH. CONCRETE PARAPETS: Concrete parapets with height-to-thickness ratios greater tha 2.5 have vertical reinforcement. (Commentary: Sec. A.7.8.3. Tier 2: Sec. 13.6.5)
C	NC	N/A	U	LS-MH; PR-LMH. APPENDAGES: Cornices, parapets, signs, and other ornamentation or appendages that extend above the highest point of anchorage to the structure or cantilever from components are reinforced anchored to the structural system at a spacing equal to or less than 6 ft. This checklist item does not apply parapets or cornices covered by other checklist items. (Commentary: Sec. A.7.8.4. Tier 2: Sec. 13.6.6)



С	NC	N/A	U	LS-LMH; PR-LMH. URM CHIMNEYS: Unreinforced masonry chimneys extend above the roof surface no more than the following: for Life Safety in Low or Moderate Seismicity, 3 times the least dimension of the chimney; for Life Safety in High Seismicity and for Position Retention in any seismicity, 2 times the least dimension of the chimney. (Commentary: Sec. A.7.9.1. Tier 2: 13.6.7)
С	NC	N/A	U	LS-LMH; PR-LMH. ANCHORAGE: Masonry chimneys are anchored at each floor level, at the topmost ceiling level, and at the roof. (Commentary: Sec. A.7.9.2. Tier 2: 13.6.7)
Sta	irs			
С	NC	N/A	U	LS-LMH; PR-LMH. STAIR ENCLOSURES: Hollow-clay tile or unreinforced masonry walls around stair enclosures are restrained out-of-plane and have height-to-thickness ratios not greater than the following: for Life Safety in Low or Moderate Seismicity, 15-to-1; for Life Safety in High Seismicity and for Position Retention in any seismicity, 12-to-1. (Commentary: Sec. A.7.10.1. Tier 2: Sec. 13.6.2 and 13.6.8)
С	NC	N/A	U	LS-LMH; PR-LMH. STAIR DETAILS: In moment frame structures, the connection between the stairs and the structure does not rely on shallow anchors in concrete. Alternatively, the stair details are capable of accommodating the drift calculated using the Quick Check procedure of Section 4.5.3.1 without including an lateral stiffness contribution from the stairs. (Commentary: Sec. A.7.10.2. Tier 2: 13.6.8)
Coi	ntents	s and I	Furn	ishings
С	NC	N/A	U	LS-MH; PR-MH. INDUSTRIAL STORAGE RACKS: Industrial storage racks or pallet racks more than 12 f high meet the requirements of ANSI/MH 16.1 as modified by ASCE 7 Chapter 15. (Commentary: Sec. A.7.11.1. Tier 2: Sec. 13.8.1)
С	NC	N/A	U	LS-H; PR-MH. TALL NARROW CONTENTS: Contents more than 6 ft high with a height-to-depth or heighto-width ratio greater than 3-to-1 are anchored to the structure or to each other. (Commentary: Sec. A.7.11.2. Tier 2: Sec. 13.8.2)
С	NC	N/A	U	LS-H; PR-H. FALL-PRONE CONTENTS: Equipment, stored items, or other contents weighing more than 20 lb whose center of mass is more than 4 ft above the adjacent floor level are braced or otherwise restrained (Commentary: Sec. A.7.11.3. Tier 2: Sec. 13.8.2)
С	NC	N/A	U	LS-not required; PR-MH. ACCESS FLOORS: Access floors more than 9 in. high are braced. (Commentary: Sec. A.7.11.4. Tier 2: Sec. 13.8.3)
С	NC	N/A	U	LS-not required; PR-MH. EQUIPMENT ON ACCESS FLOORS: Equipment and other contents supported by access floor systems are anchored or braced to the structure independent of the access floor. (Commentary: Sec. A.7.11.5. Tier 2: Sec. 13.7.7 and 13.8.3)
С	NC	N/A	U	LS-not required; PR-H. SUSPENDED CONTENTS: Items suspended without lateral bracing are free to swin from or move with the structure from which they are suspended without damaging themselves or adjoining components. (Commentary, A.7.11.6. Tier 2: Sec. 13.8.2)
Me	chani	cal an	d El	ectrical Equipment
С	NC	N/A	U	LS-H; PR-H. FALL-PRONE EQUIPMENT: Equipment weighing more than 20 lb whose center of mass is more than 4 ft above the adjacent floor level, and which is not in-line equipment, is braced. (Commentary: A.7.12.4. Tier 2: 13.7.1 and 13.7.7)
С		N/A	U	LS-H; PR-H. IN-LINE EQUIPMENT: Equipment installed in-line with a duct or piping system, with an operating weight more than 75 lb, is supported and laterally braced independent of the duct or piping system (Commentary: Sec. A.7.12.5. Tier 2: Sec. 13.7.1)
С	NC	N/A	U	LS-H; PR-MH. TALL NARROW EQUIPMENT: Equipment more than 6 ft high with a height-to-depth or height-to-width ratio greater than 3-to-1 is anchored to the floor slab or adjacent structural walls. (Commentary: Sec. A.7.12.6. Tier 2: Sec. 13.7.1 and 13.7.7)
С	NC	N/A	U	LS-not required; PR-MH. MECHANICAL DOORS: Mechanically operated doors are detailed to operate at a story drift ratio of 0.01. (Commentary: Sec. A.7.12.7. Tier 2: Sec. 13.6.9)

### West Side Fire Department - Station #2

January 23, 2018






### A. ASCE 41-13 CHECKLIST

С	NC	N/A	U	LS-not required; PR-H. SHAFT WALLS: Elevator shaft walls are anchored and reinforced to prevent toppling into the shaft during strong shaking. (Commentary: Sec. A.7.16.5. Tier 2: 13.8.6)
С	NC	N/A	U	LS-not required; PR-H. COUNTERWEIGHT RAILS: All counterweight rails and divider beams are sized in accordance with ASME A17.1. (Commentary: Sec. A.7.16.6. Tier 2: 13.8.6)
С	NC	N/A	U	LS-not required; PR-H. BRACKETS: The brackets that tie the car rails and the counterweight rail to the structure are sized in accordance with ASME A17.1. (Commentary: Sec. A.7.16.7. Tier 2: 13.8.6)
С	NC	N/A	U	LS-not required; PR-H. SPREADER BRACKET: Spreader brackets are not used to resist seismic forces. (Commentary: Sec. A.7.16.8. Tier 2: 13.8.6)
С	NC	N/A	U	LS-not required; PR-H. GO-SLOW ELEVATORS: The building has a go-slow elevator system. (Commentary: Sec. A.7.16.9. Tier 2: 13.8.6)

This page intentionally left blank.



https://earthquake.usgs.gov/cn1/designmaps/us/summary.php?template=minimal&latitude=45.68567970430144&longitude=-121.5271935&siteclass=3... 1/1



/9/2017			Design Maps Detailed Re	port		
<b>EVSGS</b> Design Maps Detailed Report						
ASCE 41-13 Retrofit Standard, BSE-1N (45.68568°N, 121.52719°W)						
Site Class D – "Stiff Soil"						
Section	2.4.1 – Ge	eneral Procedure for	Hazard Due to Ground	Shaking		
Provideo	l as a refere	ence for Equation (2-4)	and Equation (2-5), res	pectively:		
From	Section 2.	4.1.1		$S_{s,BSE-2N} = 0.552 \text{ g}$		
From	Section 2.	4.1.1		$S_{1,BSE-2N} = 0.252 \text{ g}$		
Section	2.4.1.6 -	Adjustment for Site	Class			
the defa	ult has classif		S), site-specific geotechnica D, based on the site soil pi			
SITE CLASS	SOIL PROFILE NAME	Soil shear wave velocity, v <sub>s</sub> , (ft/s)	Standard penetration resistance, <i>N</i>	Soil undrained shear strength, s <sub>u</sub> , (psf)		
А	Hard rock	$\overline{v}_{s} > 5,000$	N/A	N/A		
В	Rock	$2,500 < \overline{v}_{s} \le 5,000$	N/A	N/A		
С	Very dense soil and soft rock	$1,200 < \overline{v}_{s} \le 2,500$	<u></u> <i>N</i> > 50	>2,000 psf		
	Stiff soil	$600 \le \overline{v}_{\rm S} < 1,200$	$15 \le \overline{N} \le 50$	1,000 to 2,000 psf		
D	profile			<1,000 psf		
D	profile Stiff soil profile	$\overline{v}_{\rm S}$ < 600	$\overline{N}$ < 15	<1,000 psi		
	Stiff soil		$\overline{N}$ < 15 an 10 ft of soil having the cha			
E	Stiff soil		an 10 ft of soil having the cha 20, ≥ 40%, and			
E	Stiff soil	Any profile with more that 1. Plasticity index $PI >$ 2. Moisture content $w \ge$ 3. Undrained shear stree	an 10 ft of soil having the cha 20, ≥ 40%, and	aracteristics:		

https://earthquake.usgs.gov/cn1/designmaps/us/report.php?template=minimal&latitude=45.68567970430144&longitude=-121.5271935&siteclass=3&ri... 1/4

### West Side Fire Department - Station #2

### 11/9/2017

### Design Maps Detailed Report

Table 2–3. Values of  $\rm F_a$  as a Function of Site Class and Mapped Short-Period Spectral Response Acceleration  $\rm S_s$ 

Site	Mapped Spectral Acceleration at Short-Period $S_{\scriptscriptstyle{S}}$						
Class	S <sub>s</sub> ≤ 0.25	$S_{s} = 0.50$	$S_{s} = 0.75$	$S_{s} = 1.00$	S <sub>s</sub> ≥ 1.25		
A	0.8	0.8	0.8	0.8	0.8		
В	1.0	1.0	1.0	1.0	1.0		
С	1.2	1.2	1.1	1.0	1.0		
D	1.6	1.4	1.2	1.1	1.0		
Е	2.5	1.7	1.2	0.9	0.9		
F	Site-specific geotechnical and dynamic site response analyses shall be						

performed

Note: Use straight-line interpolation for intermediate values of S<sub>s</sub>

For Site Class = D and S<sub>s</sub> = 0.552 g, F<sub>a</sub> = 1.359

Table 2–4. Values of  $\rm F_v$  as a Function of Site Class and Mapped Spectral Response Acceleration at 1 s Period S\_1


Site	Mapped Spectral Acceleration at 1 s Period $S_1$						
Class	S <sub>1</sub> ≤ 0.10	S <sub>1</sub> = 0.20	S <sub>1</sub> = 0.30	S <sub>1</sub> = 0.40	S <sub>1</sub> ≥ 0.50		
A	0.8	0.8	0.8	0.8	0.8		
В	1.0	1.0	1.0	1.0	1.0		
С	1.7	1.6	1.5	1.4	1.3		
D	2.4	2.0	1.8	1.6	1.5		
Е	3.5	3.2	2.8	2.4	2.4		
F	Site-specific geotechnical and dynamic site response analyses shall be performed						

Note: Use straight-line interpolation for intermediate values of S<sub>1</sub>

For Site Class = D and S $_{\rm 1}$  = 0.252 g,  $F_{\rm v}$  = 1.896

 $https://earthquake.usgs.gov/cn1/designmaps/us/report.php?template=minimal&latitude=45.68567970430144&longitude=-121.5271935&siteclass=3&ri\dots 2/4$ 






 $T_s = 0.634$ 

Period, T (sec)

https://earthquake.usgs.gov/cn1/designmaps/us/report.php?template=minimal&latitude=45.68567970430144&longitude=-121.5271935&siteclass=3&ri... 3/4

### West Side Fire Department - Station #2

 $T_0 = 0.127$ 



https://earthquake.usgs.gov/cn1/designmaps/us/report.php?template=minimal&latitude=45.68567970430144&longitude=-121.5271935&siteclass=3&ri... 4/4



Portland, OR Architect 503.224.9560	ure = Interiors = Plar	nning		ne 11/8/17 0#2170545.0	
HOOD RIVER FIRE STAT	MON 2			SIW	
TOTAL	ILE. OPSF	1	SEISMIC DEA SEXCLUDE 1/2 MECHA TOTAL = 14.0PSF	ELEC, SPRINKLER,	MISC :
MECH/ELEC FIRE SPRINKLER MISC	2.0PSF 1.0PSF 1.9PSF				
WOOD JOISTS . BLOCKING	3.3 PSF 0.5 PSF		14" TJI @ 2×4'S @4		
CEILING	1.6PSF		ACOUSTIC	-IBER TILE	
SHEATHING	1.SPSF		1/2" PLY		
INSULATION	1.5PSF		ASSUMED	1" RIGID	
ROOFING	2.5PSF		BUILT UP	ROOF	
LOW ROOF WOOD DECK DEA	DLOADS				
			MISC. TOTAL = 17.		
TOTAL	19.0PSF	Ť	SEISMIC DE SEXCUDE 1/2 N MISC.		RINKLER
MISC	1.5 PSF		CEICLAIL DE		
FIRE SPRINKLER	I.OPSF				
MECH/ELEC	2.0PSF		LIGHTS 3	FIFING	
BLOCKING	0.5 PSF		2×4'5 @4		
OUTRIGGERS	I.7PSF		2×6'5 @16		
WOOD JOISTS	4.0 PSF		32" TJL'S (		
CEILING	2.8PSF		5/8" GYP		
SHEATHING	I.SPSF		1/2" PLY		
INSULATION	1.5 PSF		ASSUMED	I" RIGID	
ROOFING	2.5 PSF		BUILT UP P		
PADEINIC	OFDOE		RINIT NO D	AAC	

### West Side Fire Department - Station #2

NOOD WALLS	FULL H	EIGHT (HIGH ROT	OF)	FULL HEIGHT (LO	W ROOF )
	NORTH	WALL: L: 58.7', ht:	19.11	INTERIOR WALLS :	
	SOUTH	WALL : L = 58.7', ht:	14.7'		ht = 10.7
	EZW WI	ALLS: L= 90.71, ht =	19.4	EXTERIOR WALLS : 2=170.7	
		EAST WALL SHARED		(ALL LOW ROOF) ht= 8	
LOADS .					
2×6016	"O.C.	1.7PSF			
5/8" GYP		2.8 PSF			
1/2" PLY		1.5 PSF			
5/8" PLY		I. 8 PSF			
R-II INSUL	-	3.0PSF			
MISC		I.2 PSF			
TOTAL		12.0 PSF			
SEISMIC WE	IGH DISTRI	IBUTION OF WAL	LS :		
HIGH ROO	F LAPP BAY	3) : (0.8k + 1.5k + 1	2.4K+	10.6k = 21.3k	
L	OW ROOM	F: 1.5k + 2.4k+	10.5×	+ 9.1K = 23.5K	
SEISMIC WEI	HT DISTR	IBUTION OF ROOM	FS :		
	1			2.7')(59.1'+8') = 6:	3.0k
				'+5.4') - (58.7')(52	
				0.17 (000. 1(02.	

HOOD RI	VER FIR	E STATION 2	By SIW
	Portland, OR 503.224.9560	Architecture = Interiors = Planning = Engineering	Date_11/8/17
	Vancouver, WA 360.695.7879		Job # 2170545.00
www.mcknze.com	Seattle, WA 206.749.9993	MACKENZIE.	©2017 MACKENZIE. ALL RIGHTS RESERVED


### Seismic Assessment 2170545.00

Μ.


B-9

SHEAR STRESS QUICK CHECK
SEC 4.5.2.4:
B= 0.75
$C_{t} = 0.02$
$h_n = 22'$
$T = C_{t}h_{n}^{\beta} = 0.203s$ (EQN 4.5)
SEC 4.5.2.3.
Sxs, ESE-IN = 0.4999 (USGS REPORT) OVERTURNING CHECK
SX1, BSE.IN = 0.3199 (USGS REPORT) 0.299 < 6.08/19.1"
$S_a = S_{x1}/T = 1.57 \ 7 \ S_{xs} \Rightarrow S_a = S_{xs} (EQN 4.4)$ O.299 < 0.310 $\therefore COMPUANT$
SEC .4.5.2.1:
C = 1.3
W = 21.3k + 23.5k + 63.0k + 47.9k = 155.7k
V=CSaW=0.6487W=101.04
SEC 4.5.2.2:
LEVEL hx(f+) Wx(k) Wxhxk Cvx Fx(k)
HIROOF 22' 89.3k 1854.6k 0.689 69.1k
LOWROOF 12' 71.4K 856.8K 0.316 31.9K
Z12711.4k Z101.0k
⇒ CHANGE IN MASS < 50% FLOOR TO FLOOR MASS IS COMPLIANT
HOOD RIVER FIRE STATION 2     By SIW       Portland, OR 503.224.9560 Vancouver, WA 360.695.7879     Architecture = Interiors = Planning = Engineering Job # 2170545.00
Seattle, WA       Seattle, WA       MACKENZIE       Shtof         206.749.9993       ©2 017 Mackenzie. All rights reserved


### West Side Fire Department - Station #2









### West Side Fire Department - Station #2



### Seismic Assessment 2170545.00











B-15



NEST SIDE OF HIGH RO	NOF		
Dead Load: Pull:	$= \left[17 \cdot \text{psf} \cdot \left(\frac{1.33 \cdot \text{ft}}{2} + 4 \cdot \text{ft}\right) \cdot 23.66 \cdot \text{ft}\right] + \left(14 \cdot \text{psf} \cdot \frac{20 \cdot \text{ft}}{2} \cdot 23.66 \cdot \text{ft}\right]$	$ft + (150 \cdot pcf \cdot 0.33 \cdot ft \cdot 8)$	$ft \cdot 23.66 \cdot ft) = 14.558 \cdot k$
Live Load: Pil:=	= 0·k	Footing Width:	$W := 2 \cdot ft$
Total Load: Pt.:=	P., + P.,	Length:	$L := 25.66 \cdot \text{ft}$
	14.558·k	Thickness:	t;= 8·in
ť	$P_{WW} = 1.2 \cdot P_{dl} + 1.6 \cdot P_{ll}$	Eccentricity of col. to center line of Ftg	e <sub>fta</sub> ∷= 0·ft
	$P_u = 17.47 \cdot k$	Concrete Strength:	f.:= 3⋅ksi
Applied Moment:	$M_{\rm M} := (34.63 \cdot k \cdot 21.7 \cdot ft) + (15.75 \cdot k \cdot 11.8 \cdot ft) = 937.321 \cdot k \cdot ft$	Steel	f .:= 60∙ksi
Soil Bearing:	$g_{all} := 1500 \cdot psf \cdot 1.33$	Steel Depth:	$d := t - 3 \cdot in75 \cdot in \cdot 1.$ $d = 3.875 \cdot in$
Wt. of Conc.	Access:= 150·pcf	Column Size	$d = 3.875 \cdot \text{in}$





### West Side Fire Department - Station #2


Flexure (per 1' width) ACI 318-11 15.4.1, 15.4.2a ACI 318-14 13.2.6.4, 13.2.7.1  $M_{W} := q_{u} \left(\frac{W-c}{2}\right)^{2} \cdot \frac{1}{2} \cdot 1 \cdot ft$  $M_{\rm u} = 0.223 \cdot \rm{lk}$  $\textbf{Find}\, \textbf{As}_{\textbf{req}} \colon \quad \underbrace{f}(A_{sreq}) \coloneqq A_{sreq} \cdot f_y \cdot \left[ d - \frac{A_{sreq} \cdot f_y}{.85 \cdot f_c \cdot (1 \cdot ft) \cdot 2} \right] \cdot .9 - M_u$ f(p) = 0 g(p) := Find(p)  $A_{\text{second}} := g(1 \cdot in^2)$ Given Use #5's @ 12" oc  $A_{sreq} = 0.013 \cdot in^2$   $A_{sreq} = 0.013 \cdot in^2$  $\frac{A_{sreq}}{A_{s}} = 0.041$  $check_{f_s} = if(A_s \ge A_{sreq}, "OK", "NG")$  $check_f = "OK"$  $\rho := \frac{A_s}{(1:ft)\cdot d} \qquad \rho = 0.0067$ ACI 318-11 eqn (10-3) pmin:= .0018 ACI 318-14 9.6.1.2 check<sub> $\rho_{\mu}$ </sub> := if ( $\rho \ge \rho_{min}$ , "OK", "NG")  $check_{\rho} = "OK"$ WEST SIDE OF HIGH ROOF

WOOD DIAPHRAGM SHEAR CHECK	
M=1.25 (WOOD STRUCTURAL PANEL, BLOCKED, UNCHORDE	D)
k=1.0	
Qc = 600PLF (1/2" STRUCT SHEATHING WIASSUMED NA @6"0.C.)	ALLING OF 8d NAILS
MKQc = 750PUF < 1112PUF = Qu : WOOD DIAPHRACIM ASSUMED PROFERTIES => RE-NAIL, ADD CHORD ELEMENTS	IS DEFICIENT WI
M=1.5 (WOOD STRUCTURAL PANEL, BLOCKED, CHORD	ED)
mkQc = 800PUF(1.5)(1.0) = 1200PUF > 1112PUF = Qu	and when the second
: 1/2" STRUCT SHTY, BLOCKED, W/ NAILS @ 4"O.C.	@ PANEL EDGES
	,
	-
HOOD RIVER FIRE STATION 2	By SIW
Portland, OR 503.224.9560 Architecture = Interiors = Planning = Engineering	Date 11/10/17
www.mcknze.com	Job #_2170545.00 Shtof ©2017 Mackenzie. All rights reserved

### West Side Fire Department - Station #2

HOLD-DOWN ANCHORAGE	
@ WALL ()	
0.9MST > MOT/(C, C2, MOT)	
$M_{ST} = \left[ 12PSF(12')(8.66') + 14PSF(0.66')(12') \right] (6') = 814'$	$8^{\#-f_1} = 8.15 \text{ k}-f_1$
Mot = 13.2k(121) = 158k-F+	
$C_1 C_2 = 1.1$	
$M_{OT} = 4.0$	
$0.9M_{ST} = 7.34 k - A$	
Mor/(C, C2, Mor) = 35.9K-Ft > 7.39K-Ft : OVERTURNIN	19, HOLDOWNS READ
@ WALL ()	
MST = [12PSF (19,41) (45.33') + 17 PSF (0, lele' + 41) (45.33')]	(45.33/2) = 320,570 + A= 320.57 kft
Mot = 46,4k (21.6) = 1602.3k-fr	
0.9MST = 2 BB. 5K-Ft	
Mot/(C1C2Mot) = 228 K-A < 288.5 K-A .: NO OVER	DRHINLY
OWAL (5)	
$M_{ST} = \left[ 12PSF(14.7')(30.17') + 17PSF(45.33'/2)(30.17') + 14PSF \right]$ = 317,221 <sup>#-F+</sup> = 317.22 <sup>k-F+</sup>	$(19.33'_{2})(30.17')](30.17'_{2})$
$M_{oT} = 48.9 \times (17.2!) = 841.1 \text{ k-fr}$	
$0.9M_{st} = 285.5k-F_{-}$	
Mot 1(C1 C2 Mot) = 191.2k-Ft < 285.5k-Ft NO OVEK	2 TO VENING
1010T TCC (2,2,2,0) - TTT 2 - 200.0	
HOOD RIVER FIRE STATION 2	By SIW
Portland, OR 503.224.9560 Vancouver, WA 360.695.7879	Date 118/17 Job # 2170 545.00
Seattle, WA 206.749.9993 MACKENZIE.	ShtOf ©2017 Mackenzie. All rights reserved





### West Side Fire Department - Station #2

CHORD FOR CES  
HIGH ROOF:  
N=5 CONDITION  


$$M = 1.18^{1/4} (55.7)^{1/3} = 508.3^{1.6}$$
  
 $T = C : 506.3^{1.6} / (45.57)^{1/3} = 508.3^{1.6}$   
 $T = C : 506.3^{1.6} / (45.57)^{1/3} = 508.3^{1.6}$   
 $T = C : 506.3^{1.6} / (45.53)^{1/3} = 30.3^{1.6}$   
 $M = 1.53^{1/6} (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $T = C : 393^{1.2} / (45.53)^{1/3} = 30.3^{1.6}$   
 $F_{1} = 10^{1/3} / (45.4)^{1/3} = 50.700$   
 $F_{2} = 10^{1/3} / (45.4)^{1/3} = 50.707$   
 $F_{1} = 1350 \rho_{1} : (0.915) = 1343 \rho_{1} : (1.12^{1.6} / (1.12^{1.6} / (1.12^{1.6} - (1.12^{1.6} / (1.12^{1.6} - (1.12^{1.6$ 

### Seismic Assessment 2170545.00



CHORD FORCES LOWER ROOF: N-S CONDITION M= 0.4 k/f+ (78.7')2/ = 309.68 k-f+ T= C = 309.7k' /19.33' = 16.02 K < +Th FOR CMST12 E-W CONDITION M: 0.44 k/4 (72')2/8 = 285.12k-A T= C= 285.12k- 4/20 = 14.3k < 4 Th FOR CMST12 CHECK 4+6 BLOCKING FOR COMPRESSION fc= 16.02 ((3.5") (5.5") = 832 psi < Fc1 : 4 × 6 BLOCKING @ STRAP By SIW Portland, OR Date 11/17/17 Architecture = Interiors = Planning = Engineering 503.224.9560 Vancouver, WA Job# 360.695.7879 Seattle, WA MACKENZIE. Sht. of ©2017 Mackenzie. All rights reserved www.mcknze.com 206.749.9993

### West Side Fire Department - Station #2





MOMENT FRAME

TOTAL LATERAL LOAD :  $34.7^{k}$  (ASCE 41 LOAD) ASSUME (2) BAYS OF MF'S @ NORTH EPGE LIMITING DEFLECTION (ASCE 7) :  $\Delta_{\alpha} = 0.015h_{sx} = 0.015(21.7')(12''/f_{+}) = 3.9''$ COLUMNS: W21 × 68BEAMS: W18 × 46BEAMS: W18 × 46GRADE BEAM : 30'' × 30'' CONCRETE

 $S_{M} = \frac{CdS_{MAX}}{Ie} = \frac{5.5(0.936')}{1.5} = 3.43'' < 3.9'' - OK$ 

HOOD RIVI	ER FIRE	STATION 2	$_{\rm By} \leq   \mathcal{N} /$
M	Portland, OR 503.224.9560 Vancouver, WA 360.695.7879	Architecture « Interiors « Planning » Engineering	Date 11/10/17 Job # 2170545.00
www.mcknze.com	Seattle, WA 206.749.9993	MACKENZIE.	Shtof ©2017 Mackenzie. All rights reserved

### West Side Fire Department - Station #2

### MACKENZIE.

DESIGN DRIVEN I CLIENT FOCUSED

RiverEast Center 1515 SE WaterAve. - P.O. BOX 14310 Portland, OR 97293 TEL (503) 224-9560 - FAX (503) 228-1285

### MOMENT FRAME FOUNDATION

PROJECT NAME: Hood River Station 2 PROJECT NO.: 2170545.00

DESIGNER: SIW DATE: 11/16/17

Unit Definitions -

### **GENERAL**


- f<sub>y e</sub> := 40ksi Reinforcing Yield Strength Existing
- $f_{v n} := 60 ksi$  Reinforcing Yield Strength New
- $E_s := 29000 ksi$  Reinf. Modulus of Elasticity
- DL<sub>rf\_sei</sub> := 17psf Roof Seismic Dead Load
- know := 1.0 Knowledge factor
- $q_{all} := 1500 psf$  Allowable soil pressure
- f<sub>c</sub> := 3000psi Concrete Compressive Strength
- $f_{ce} := 1.5 \cdot f_c = 4500 \cdot psi$  Concrete expected strength

✓ Moment Frame At North Side			
1) Overturning Analysis			
$ht_{rf} := 21.7 ft$	Roof Height		
$w_s := 16.66 \cdot ft$	Width of Moment	Frame	
$V_{rf} := 17.35k$	Ultimate Shear @	Roof	
	Total Base Shear		
$V_{tot} := V_{rf}$ $V_{tot} = 17.35 \cdot k$ $M_{ot} := V_{rf} \cdot ht_{rf}$ $M_{ot} = 376.5 \cdot k \cdot ft$	Overturning Mome	ent	
( 15 22 8	-		
	$P_{\rm D} = 6.419 \cdot k$		
$P_{L} := 0$	$P_L = 0 \cdot k$		
$P_{S} := P_{D} \cdot \frac{25psf}{DL_{rf\_sei}}$	$P_S = 9.44 \cdot k$		
$P_E := \frac{M_{ot}}{w_s}$	$P_{\rm E} = 22.599 \cdot k$		
$P_{slab} := 6in \cdot 0.15kcf \cdot 5ft \cdot 0.5 \cdot w_s$	$P_{slab} = 3.124 \cdot k$	Additional over	erturning resistance from slab
Gravity Footing Calcs			
$A_{grav} := \frac{P_D + P_L + P_S}{q_{rav}}$		$A_{grav} = 10.573 \text{ ft}^2$	
q <sub>all</sub> Seismic Footing Calcs - Footing @		grav	
CC <sub>12</sub> := 1.1			Table 7-3
$\mu_{ot} := 4$ pg 99 (10.0 = Collaps	se, 8.0 = Life Safety,	4.0 = I.O.)	
$m_{frg} := 1.5$ Section 8.4.2.3.2.1	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,	
$w_{ftg} := 2.5 ft$			Footing Width
$d_{fig} := 30 in$			Footing Depth
$l_{ftg} := 3 ft$			Footing Length
$P_{ftg} := l_{ftg} \cdot d_{ftg} \cdot w_{ftg} \cdot 150 pcf$		$P_{ftg} = 2.8 \cdot k$	Footing Weight
$\mathbf{P}_{\text{tot}} := \left(1.1\mathbf{P}_{\text{D}} + 1.1\mathbf{P}_{\text{ftg}} + \mathbf{P}_{\text{E}}\right)$	l	$P_{tot} = 32.75 \cdot k$	
$\mathbf{M}_{\text{res}} \coloneqq \left(\mathbf{P}_{\text{D}} + \mathbf{P}_{\text{slab}}\right) \cdot \frac{\mathbf{w}_{\text{s}}}{2} + \left(\mathbf{P}_{\text{ftg}} \cdot \mathbf{w}_{\text{s}}\right)$		$M_{res} = 126.349 \cdot k \cdot ft$	Overturning Resistive Moment
$DCR_{OT} := \frac{M_{ot}}{0.9M_{res} \cdot (CC_{12} \cdot \mu_{ot})}$		$\text{DCR}_{\text{OT}} = 0.752$	EQ 7-6
$OT := if(1.0 \ge DCR_{OT}, "OK", "NO GOOD")$		OT = "OK"	Overturning check

### West Side Fire Department - Station #2

$q := \frac{P_{tot}}{l_{ftg} \cdot w_{ftg}}$ $DCR_{FTG} := \frac{q}{m_{ftg} \cdot 3q_{all}}$	$q = 4367 \cdot psf$ DCR <sub>FTG</sub> = 0.647	Soil Pressure, Resultant Inside Central Kern
$BEARING := if(DCR_{FTG} \le 1.0, "OK", "NG!!!")$	BEARING = "OK"	Check Temporary Load Soil Pressure
Design Footing Reinforcement (ACI 318-08) $q_u \coloneqq q$	q <sub>u</sub> = 4367.1∙psf	Factor Soil Bearing Pressure (cons) By 1.4 to Bring to Ultimate
$d_b := 0.625  \text{in}$		Diameter of Reinforcing Bar
$d := d_{ftg} - 3in - \frac{3 \cdot d_b}{2}$	$d = 26.1 \cdot in$	Depth to Reinforcing
Beam Shear		
$\phi_{vc} \coloneqq 1.0 \qquad \qquad \phi_b \coloneqq 1.0$		
$V_{u} := q_{u} \cdot max(l_{ftg}, w_{ftg}) \cdot 1 ft$	$V_u = 13.101 \cdot k$	Ultimate Shear per Foot of Overhang Width (can take at d
$V_c := 2 \cdot \sqrt{\frac{f_{ce}}{psi}} \cdot d \cdot 1 \text{ ft} \cdot psi$	$V_c = 41.96 \cdot k$	from face of support if needed!)
	$\phi V_c = 41.96 \cdot k$	Shear Strength of Concrete per Foot - 11.2.1.1, p. 158
SHEAR := if $(\phi V_c > V_u, "OK", "NG!!!")$	SHEAR = "OK"	
Flexure		
$\beta_1 := 0.65$ if $f_c \ge 8000$ psi	$\beta_1 = 0.85$	
0.85 if $f_c \le 4000$ psi		
$0.85 - \frac{.05 \cdot \left(\frac{f_c}{psi} - 4000\right)}{1000}  \text{otherwise}$		Beta,10.2.7.3, p. 131
$M_{u} := q_{u} \cdot \frac{\max(l_{ftg}, w_{ftg})^{2}}{2} \cdot 1  ft$	$M_u = 19.652 \cdot k \cdot ft$	Ulitmate Moment per Foot of Overhang Width
Function to Solve RC Beam Area of Steel Required - 10.2, p.	129	
$f(A_s) := A_s \cdot f_{y_n} \cdot \left( d - \frac{A_s \cdot f_{y_n}}{0.85 \cdot f_c \cdot 1 ft \cdot 2} \right) \cdot \phi_b \cdot m_{ftg} - M_u$		
Given $f(p) = 0$ $g(p) := Find(p)$ $A_s := g(1in^2)$	$A_{\rm s} = 0.101 \cdot {\rm in}^2$	Area of Steel Required for Strength per Foot
<mark>,‰:= 12in</mark>		Bar Spacing - 10.5.4, p. 135
A <sub>bar</sub> := 0.44in <sup>2</sup> Use #6 at 12" o.c. Each Way Top	and Bottom!	(max spacing is 18" or 3d <sub>ftg</sub> )





### West Side Fire Department - Station #2


**Flexure**  $\beta_{\rm M} := \begin{bmatrix} 0.65 & \text{if } f_{\rm c} \ge 8000 \text{psi} \\ 0.85 & \text{if } f_{\rm c} \le 4000 \text{psi} \\ 0.85 - \frac{.05 \cdot \left(\frac{f_{\rm c}}{\text{psi}} - 4000\right)}{1000} & \text{otherwise} \end{bmatrix}$  $\beta_1 = 0.85$ Beta, 10.2.7.3, p. 131 Function to Solve RC Beam Area of Steel Required - 10.2, p. 129  $f(A_s) := A_s \cdot f_{y_n} \cdot \left( d - \frac{A_s \cdot f_{y_n}}{0.85 \cdot f_c \cdot w_{hm} \cdot 2} \right) \cdot \phi_b \cdot m_{ftg} - M_u$ Given f(p) = 0 g(p) := Find(p)  $A_{ss} := g(1in^2)$ Area of Steel Required for  $A_s = 0.631 \cdot in^2$ Strength per Foot  $A_{\text{softg}} = 0.44 \text{in}^2 \cdot (8)$  $A_{s ftg} = 3.52 \cdot in^2$ Area of Steel Provided per Foot  $REINF := if (A_{s ftg} \ge A_{s}, "OK", "NG!!!")$ REINF = "OK" $\mathbf{x} := \frac{\mathbf{A}_{s_{ftg}} \cdot \mathbf{f}_{y_n}}{0.85 \cdot \mathbf{f}_{o} \cdot \boldsymbol{\beta}_1 \cdot \mathbf{w}_{hm}}$  $c = 3.248 \cdot in$ Neutral Axis Location  $flag := if\left(\frac{c}{d} < 0.375, "Tension Controlled", if\left(\frac{c}{d} > 0.6, "Compression Controlled", "Transition"\right)\right)$ flag = "Tension Controlled"  $A = \begin{bmatrix} 0.9 & \text{if } \frac{c}{d} < 0.375 \\ 0.65 & \text{if } \frac{c}{d} > 0.6 \\ 0.23 + \frac{0.25}{\frac{c}{d}} & \text{otherwise} \end{bmatrix}$  $\phi_b = 0.9$ Strength Reduction Factor -R9.3.2.2, p. 118  $M_{\text{WW}} = A_{s_{\text{ftg}}} f_{y_{n}} \left( d - \frac{c \cdot \beta_{1}}{2} \right)$  $M_n = 436.605 \cdot k \cdot ft$ Nominal Moment Capacity per Foot  $\phi M_{n} := m_{ftg} \cdot \phi_b \cdot M_n$  $\phi M_n = 589.42 \cdot k \cdot ft$ Moment Capacity per Foot FLEXURE := if  $(\phi M_n > M_u, "OK", "NG!!!")$ FLEXURE = "OK" Moment Frame At North Side



This page intentionally left blank.


## C. UPGRADE SCHEME

This page intentionally left blank.





### C. UPGRADE SCHEME




### West Side Fire Department - Station #2


	Keynotes
#	Description
1	REMOVE SIDING, ADD BLOCKING AS REQUIRED & RENAIL SHEATHING @ 3" O.C. AT WOOD SHEAR WALLS HIGHLIGHTED IN RED.
2	REMOVE EXISTING SHEATHING. ADD BLOCKING, REPLACE SHEATHING W/ 19/32" PLYWOOD SHEATHING W/ 10D NAILS @ 4" O.C. AT WOOD SHEAR WALLS HIGHLIGHTED IN BLUE.
3	ADD SILL ANCHORS AT HIGHLIGHTED SHEAR WALLS FROM KEYNOTES 1 &2. ASSUME 1/2" DIA SIMPSON TITEN HD @ 3'-0" O.C.
4	PROVIDE HOLDOWNS AT EA END OF WALL PIERS WHERE SHOWN, ASSUME SIMPSON HDU5-SDS2.5 W/ 5/8" DIA EPOXY ANCHOR AND 12" EMBEDMENT.
5	PROVIDE STRAPPING @ WINDOWS, TYP. ASSUME SIMPSON LSTA24 EA CORNER.
6	DEMO (E) WINDOW, INFILL WITH WOOD STUD WALL & SHEATHING TO MATCH ADJACENT WALLS. PROVIDE STRAPPING, ASSUME SIMPSON LSTA24 EA CORNER.
7	4'-0" WIDE x 2'-6" THICK GRADE BEAM W/ (8) #6 LONGITUDINAL TOP & BOT & #4 TIES @6" O.C. DEMO EXISTING FOOTING TO INSTALL MOMENT FRAME. EXISTING WOOD TRUSSES MAY HAVE TO BE SHORED.
8	SEE SIMPSON MOMENT FRAME (SK4) FOR PRELIMINARY COLUMN SIZES AND BASE CONNECTION.
9	DEMO EXISTING SLAB & REPLACE SLAB W/ 6" SOG.
10	REPLACE EXISTING APP BAY DOORS (3) TOTAL.
11	FULL HEIGHT HSS 8x8x5/16 COLUMN @ DRAG BEAM.
12	W12x45 MOMENT FRAME BEAMS, TYP. SEE ATTACHED SIMPSON MOMENT FRAME (SK4).
13	4x12 DF-L #1 DRAG BEAM @ RE-ENTRANT CORNER.
14	DRAG BEAM CONNECTION @ WOOD STUD WALL OR HSS COLUMN WHERE OCCURS.
15	REMOVE EXISTING ROOFING, ADD 8d NAILS @ 4" O.C. @ PANEL EDGES
16	CONTINUOUS SIMPSON CMST12 STRAP @ LOCATIONS HIGHLIGHTED IN GREEN, TYP. PROVIDE MIN 4x BLOCKING (JOISTS PERPENDICULAR) OR ATTACH TO EXISTING DOUBLE TOP PLATE (JOISTS PARALLEL).

	Task S	Summary Table	Drawings	
Task #	Deficiency	Description	Keynote #	SK#
1	Load Path , Narrow Wood, Shear Walls, Shear Stress Check	North side of high roof does not have a sufficient amount of shear wall to resist seismic forces. (2) bay moment frame required @ this location.	7, 8, 9, 10, 12	4
2	Shear Stress Check, Hold Down Anchors, Wood Sill Bolts	Existing wood shear walls & diaphragms do not have enough capacity to resist seismic loads. There is no hold-down anchorage to resist overturning. Wood sill bolts are not compliant.	1, 2, 3, 4, 5, 6, 15	-
3	Load Path, Diaphragm Continuity	There is not sufficient blocking to tie the roof diaphragms to shear.	-	1, 2, 3
4	Roof Chord Continuity	There are no continuous chord elements.	16	3
5	Plan Irregularities	There are no drag elements @ re-entrant corners.	11, 13, 14	-
6	Life Safety Systems, Hazardous Materials, Ceilings, Light Fixtures, Cladding, Furnishings, Mechanical & Electrical, Ducts & Piping	Non-structural components are not properly braced or restrained to prevent lateral movement during a seismic event.	-	-







### West Side Fire Department - Station #2 January 23, 2018



### C. UPGRADE SCHEME



### West Side Fire Department - Station #2





### D. COST ESTIMATE

This page intentionally left blank.



December 18, 2017 Revision #1

### WEST SIDE FIRE DEPARTMENT FIRE STATION #2 SEISMIC UPGRADES



### STATEMENT OF PROBABLE COST

Prepared for: Mackenzie Portland, OR

Prepared by: Steve Gunn

Tum 11

President Construction Focus, Inc.

> Seismic Assessment 2170545.00



	WEST SIDE FIRE DEPARTMENT STATION #2 SEISMIC UPGRADES				1	
	517		ADE2			
		SORTED BY TASK				
		Statement of Probable Co	ost			
LOC	ITEM	DESCRIPTION	QNTY	UNIT	\$/UNIT	тота
	SEISMIC UPGRADES					
	Ви	uilding Gross Area	5,246	SF		
	Task #1 - Moment Frames					10
	Demo door	x_overhead door	3	EA	900.00	
	Demo footing	x cont ftg	39	LF	200.00	
	Sawcut & demo slab	x_6"_conc for new ftg	645	SF	12.00	
	Excavation	dig & haul		BCY	75.00	
	Backfill	crushed rock	12	TN	70.00	
	Grade beam	gb_4'w x 2'd	39	LF	60.00	
	SOG patch	6"t conc w/ reinf&dowels	645	SF	11.00	
	Simpson Strong Frame	supply & erect	1	EA	30,071.14	3
	Wall sheathing	19/32" APA rated	24	SF	2.61	
	Shoring	for moment frame install	39	LF	60.00	
	Overhead door	steel_hm frm_1/2 glz_14'x14'		EA	12,740.00	3
	Flooring	conc sealer	645	SF	3.00	
	Task #2 - Shear Walls and	l Roof				27
	Demo finish	x_siding/wrb	2,232	SF	4.41	
	Demo sheathing	x_ply sheathing	1,853		2.78	
	Salvage storage	r/r_lockers	8	EA	136.32	
	Salvage storage	r/r_appliances		EA	272.63	
	Demo roofing	x_mtl roofing/wrb	5,675	SF	2.14	1
	Salvage roof equip.	r/r_roof mt equip.	1	LS	2,500.00	
	Demo window & frame	x_ext window/frm	2	EA	272.63	
	Salvage casework	r/r_casework	10	LF	34.08	
	Salvage equip.	r/r_elec pnls/meter/switch		EA	4,500.00	
	Salvage equip.	r/r_wall ductwork/piping	1	LS	800.00	
	Salvage equip.	r/r_wall-mount HVAC unit		EA	900.00	
	Miscellaneous blocking and	-	320		7.20	
	Nailing: wall	renail existing ply sheathing	2,534	SF CF	1.18	
	Wall sheathing	19/32" APA rated	1,757	51	2.61	
	Blocking @ roof	DF 2x6	727		7.20	
	Nailing: roof	renail existing ply sheathing	5,675	SF EA	1.18	
	Strap	simp LSTA24	60	CA SE	4.66	
	Parapet wall framing	2x4 @ 16o.c.	229 24	SE	11.00	
	Infill wall framing	2x6 @ 16o.c.	24		4.95	
	Holdown Sill anabor	simp HD5-SDS2.5 w/5/8" epox _ 1/2" simp titen HD @ 36" OC	20		143.16	
	Sill anchor	casings & trims	162	LE	12.58 12.02	
	Finish carpentry Batt insulation	R-19	349	SE	12.02	
	WRB	Blueskin	2,485			
		DINESKIII	2,485	LS	2.36	
	Sealant	too/ovr bd///" rigid ing	5,904		500.00	15
	Roofing	tpo/cvr bd/4" rigid ins	<u>5,904</u> 334		26.00 8.00	15
	Flashing	prefin sht mtl	334		0.00	

ARCH: Mackenzie DWG DATE: 12/5/17 DESIGN LEVEL: Concept CONSTRUCTION FOCUS, INC. 541-686-2031 EUGENE, OREGON ESTIMATE DATE: Dec. 18, 2017 REVISION #: 1 CONST. START: 3 QTR\_19

West Side Fire Department - Station #2

2/3

### WEST SIDE FIRE DEPARTMENT STATION #2 SEISMIC UPGRADES SORTED BY TASK

Statement of Probable Cost

Downspoutsprefin sht mtl52LFSidingT1112,461SFSiding trim1x cedar420LFGypsum bd: wall5/8"_type: X LVL 424SFPaint: wallprime/2 top ct on gyp bd150SFPaint: cladding2 top ct on T1-112,461SFPlumbing fixturesremove/re-install4FIXHVAC ductingrelocate for access110LFElectrical fixtures & conduitrelocate for access10EATask #3 - Continuous Diaphragm315SFDemo finishx_siding/wrb315SFDemo sheathingx_ply sheathing315SFBlockingDF 2x4103LF	9.00 6.83 5.91 4.80 1.00 2.20 1,400.00 32.00 250.00 250.00 4.41 2.78	468 16,809 2,482 115 150 5,414 5,600 3,520 2,500 22,137
Siding trim1x cedar420 LFGypsum bd: wall5/8"_type: X LVL 424 SFPaint: wallprime/2 top ct on gyp bd150 SFPaint: cladding2 top ct on T1-112,461 SFPlumbing fixturesremove/re-install4 FIXHVAC ductingrelocate for access110 LFElectrical fixtures & conduitrelocate for access10 EATask #3 - Continuous DiaphragmDemo finishx_siding/wrb315 SFDemo sheathingx_ply sheathing315 SFBlockingDF 2x4103 LF	5.91 4.80 1.00 2.20 1,400.00 32.00 250.00 4.41 2.78	2,482 115 150 5,414 5,600 3,520 2,500 22,137
Gypsum bd: wall5/8"_type: X LVL 424 SFPaint: wallprime/2 top ct on gyp bd150 SFPaint: cladding2 top ct on T1-112,461 SFPlumbing fixturesremove/re-install4 FIXHVAC ductingrelocate for access110 LFElectrical fixtures & conduitrelocate for access10 EATask #3 - Continuous DiaphragmDemo finishx_siding/wrb315 SFDemo sheathingx_ply sheathing315 SFBlockingDF 2x4103 LF	4.80 1.00 2.20 1,400.00 32.00 250.00 4.41 2.78	115 150 5,414 5,600 3,520 2,500 22,137
Paint: wallprime/2 top ct on gyp bd150SFPaint: cladding2 top ct on T1-112,461SFPlumbing fixturesremove/re-install4FIXHVAC ductingrelocate for access110LFElectrical fixtures & conduitrelocate for access10EATask #3 - Continuous DiaphragmDemo finishx_siding/wrb315SFDemo sheathingx_ply sheathing315SFBlockingDF 2x4103LF	1.00 2.20 1,400.00 32.00 250.00 4.41 2.78	150 5,414 5,600 3,520 2,500 22,137
Paint: cladding       2 top ct on T1-11       2,461 SF         Plumbing fixtures       remove/re-install       4 FIX         HVAC ducting       relocate for access       110 LF         Electrical fixtures & conduit       relocate for access       10 EA         Task #3 - Continuous Diaphragm       215 SF       215 SF         Demo finish       x_siding/wrb       315 SF         Demo sheathing       x_ply sheathing       315 SF         Blocking       DF 2x4       103 LF	2.20 1,400.00 32.00 250.00 4.41 2.78	5,414 5,600 3,520 2,500 22,137
Plumbing fixtures       remove/re-install       4       FIX         HVAC ducting       relocate for access       110       LF         Electrical fixtures & conduit       relocate for access       10       EA         Task #3 - Continuous Diaphragm       Demo finish       x_siding/wrb       315       SF         Demo sheathing       x_ply sheathing       315       SF         Blocking       DF 2x4       103       LF	1,400.00 32.00 250.00 4.41 2.78	5,600 3,520 2,500 22,137
HVAC ducting       relocate for access       110       LF         Electrical fixtures & conduit       relocate for access       10       EA         Task #3 - Continuous Diaphragm	32.00 250.00 4.41 2.78	3,520 2,500 22,137
Electrical fixtures & conduit       relocate for access       10       EA         Task #3 - Continuous Diaphragm       Demo finish       x_siding/wrb       315       SF         Demo finish       x_ply sheathing       315       SF       Blocking       DF 2x4       103       LF	250.00 4.41 2.78	2,500 22,137
Task #3 - Continuous DiaphragmDemo finishx_siding/wrb315SFDemo sheathingx_ply sheathing315SFBlockingDF 2x4103LF	4.41 2.78	22,137
Demo finishx_siding/wrb315SFDemo sheathingx_ply sheathing315SFBlockingDF 2x4103LF	2.78	
Demo sheathing         x_ply sheathing         315         SF           Blocking         DF 2x4         103         LF	2.78	1 0 0 0 1
Blocking DF 2x4 103 LF	-	1,389
		876
Blocking DF 2x6 313 LF	7.10	731
	7.20	2,254 963
Blocking         DF 4x4         103         LF           Wall sheathing         19/32" APA rated         627         SF	9.38	963
Wall sheathing         19/32" APA rated         627         SF           Blocking         DF 2x6         627         SF	2.61 7.20	4,514
Blocking DF 2x6 <u>627</u> Blocking DF 4x6 312 SF	10.92	3,407
Clip A35 @ 24" OC 105 EA	5.27	553
Clip angle @ 24" OC 154 EA	5.27	812
Batt insulation R-19 315 SF	1.25	394
WRB Blueskin 315 SF	2.36	743
Sealant 1LS	500.00	500
Siding T111 315 SF	6.83	2,151
Siding trim 1x cedar 88 LF	5.91	520
Paint: cladding 2 top ct on T1-11 315 SF	2.20	693
Task #4 - Roof Chord Continuity	[	4,444
Strap CMST 12 386 LF	4.66	1,799
Blocking DF 4x4 282 LF	9.38	2,645
Task #5 - Drag Elements	[	3,370
	2,450.00	2,450
Drag beam         DF 4x12         58         LF	15.86	920
Task #6 - Non-Structural Seismic Bracing		30,468
Anchorage ceilings 5,246 SF	0.25	1,312
Anchorage equipment 9 EA	170.00	1,530
Anchorage gas cyclinders/shut-off valves 1 EA	190.00	190
Storage add shelf lips and cords <u>30 EA</u>	49.08	1,472
Glazing verification glazing meets code <u>156</u> SF	90.00	14,040
Plumbing piping     seismic bracing     118     LF       Plumbing piping     flex coupling     8     EA	14.00	1,652
	140.00	1,120
Ductwork support     seismic bracing     5,246     SF       Lighting     compliant lens covers     26     EA	0.40 180.00	2,098 4,680

ARCH: Mackenzie DWG DATE: 12/5/17 DESIGN LEVEL: Concept CONSTRUCTION FOCUS, INC. 541-686-2031 EUGENE, OREGON ESTIMATE DATE: Dec. 18, 2017 REVISION #: 1 CONST. START: 3 QTR\_19



	Generator bracing Emergency lighting	allowance				
	Emergency lighting	seismic bracing	1 5,246	EA SF	800.00 0.30	
		5	OST TOTAL		0.00	434,
	Those p Variables include fluc	RDCOST TOTAL does not include t ilus contingencies are listed below a ctuations in market conditions, mater ate Range will be consolidated as we	s part of a Low ial selections,	/-High I and de	Range. sign considera	ations.
LOW	RANGE				HIGH R	ANGE
@ 3%: @ 15%:	13,045 67,180 33,310 49,352 59,771 8,646	Markups: Inflation (1.5 years) Contingency CMGC process Gen Conditions @ 9%: Profit & Overhead @ 10 Performance Bond:	)%:	_	@ 12%: @ 30%:	52 146 40 60 73
	231,304	Markup Subtotals:		-		38
	666,127	BASE BID TOTAL				818
Hazardous n Low voltage	tion IS permit fees, system deve naterials abatement, movi electrical work. ion, rock excavation, wet	lopment fees, utility hookup charges ng expenses, anti-graffiti coating, fir weather sitework. SF=Square Feet			BCY=Bank Cu	ubic Ya
	LF= Linear Feet SY=Square Yard PR=Pair	LS=Lump Sum OPNG=Opening HT=Height		-	TN=Ton LB=Pounds	

West Side Fire Department - Station #2